	Professional Series PR 2-in-1	Contractor Series CS — 75W
Finish	**#304 Stainless Steel**	**#304 Stainless Steel**
Item Number with Wattage	**15PRD600SS** - 600W	**15CS75SS** - 75W
Input Voltage	120V	120V
Output Multi-Taps	12/13/14/15 Volts. 2 separate sets of multi-tap output with angled terminal blocks for easy wire input.	12/15 Volts
Core and Coil	High-efficiency toroid core and coil configuration	High-efficiency fully encapsulated toroidal
Door Style	Easy magnetic flip-and-stay-open door	Removable front plate with two locking screws
Easy-Connect Terminal Lug Capacity	Up to 8, #10-gauge wires or up to 10, #12-gauge wires per tap	Up to 14, #16-gauge wires per tap
Secondary Side Protection	Magnetic breaker	Magnetic breaker
Timer/Photocell	Compatible with plug-in timers and photocells. Two timer outlets for independent zone control of 2 independent lighting zones.	Integrated mechanical timer; plug-in photocell compatible
Cord	6' of usable #16-3 SJTW cord	6' of usable #18-3 SJTW cord
Conduit Knockouts	4 pre-punched field knockouts sized for .5" or .75" conduit (trade sizes) and one large center 1.75" inlet	2 pre-punched field knockouts sized for .5" or .75" conduit (trade sizes)
Notes	Includes mounting hardware. Comprised of 2-300W independently controlled transformers.	Includes mounting hardware. Dedicated wire loop for testing primary voltage. Department of Energy certified. Safety listings: cUL 1838, CSA 22.2.
Accessories	**15556WH** Digital Timer **15557BK** Mechanical Timer **15565BK** Standard Photocell **15534BK** 10' Remote Photocell **15511BK** Synchronizer	**15556WH** Digital Timer **15557BK** Mechanical Timer **15565BK** Standard Photocell **15534BK** 10' Remote Photocell **15511BK** Synchronizer
Dimensions	**21.25" L x 6.75" W x 5.75" D**	**8.23" L x 3.67" W x 4.59" D**